BROKEN CONCRETE HEADWALL

NOTE: THE LIMITS OF DISTURBANCE HAVE BEEN REVISED TO MINIMIZE ADJACENT WETLAND AND TREE IMPACTS TO THE MAXIMUM EXTENT PRACTICABLE. WETLANDS OUTSIDE THE PROJECT PERIMETER WILL NOT BE DISTURBED OR IMPACTED.

NORTH

EX. 10" SANITARY SEWER TO BE DEMOLISHED

BROKEN EX. CONCRETE HEADWALL TO BE DEMOLISHED

EX. 36" RCP STORM TO BE CUT BACK

EX. ASPHALT TO BE DEMOLISHED

EX. CONCRETE TO BE DEMOLISHED

EX. 36" CMP STORM TO BE CUT BACK

TAYLOR RUN

EX. 72" RCP STORM

EXISTING WETLAND

EX. WOODEN BRIDGE SHALL BE REMOVED AND REINSTALLED IN KIND POST-CONSTRUCTION

EX. TRAIL MARKER SHALL BE REMOVED AND REINSTALLED POST-CONSTRUCTION

EX. 4" PVC STORM

EX. HISTORIC SIGN SHALL BE REMOVED AND REINSTALLED POST-CONSTRUCTION

EX. 12" CMP STORM WITH HEADWALL

EX. PARK SIGNS TO REMAIN

MATCHLINE SEE SHEET 2

LOD

EROSION ADJACENT TO CONCRETE HEADWALL

WOODY DEBRIS ACROSS UNSTABLE EXPOSED SANITARY SEWER CROSSING

UNSTABLE STORM OUTFALL

LEGEND

- EX. 1 FT CONTOUR
- EX. STORMWATER PIPE
- EX. SEWER LINE
- SANITARY MANHOLE
- SURVEYED TREE (TO REMAIN)
- WETLANDS
- EXISTING RIPRAP
- LOD — LIMITS OF DISTURBANCE
- PROPERTY LINES
- TREE DEMOLITION
- DEMOLITION BOUNDARY
- LINEAR REMOVAL

SOURCE DATA INFORMATION
H.D. = VCS NAD 83
V.D. = NAVD 88
GIS INFO = CITY & WSSI DIG. DATA

40 20 0 40 80 120
SCALE: 1"=40'

CONCEPTUAL DESIGN

CITY OF ALEXANDRIA, VIRGINIA
DEPARTMENT OF PROJECT IMPLEMENTATION
301 KING ST., RM 3200
ALEXANDRIA, VA 22314

REVISIONS

DATE	BY	DESCRIPTION

CITY PROJECT NO.: T0-41
DATE OF PLAN ISSUANCE: XX/XX/XX
CONSULTANT PROJECT ID.: 60668730
DESIGNED BY: ST DATE: 2/4/22
DRAWN BY: ST DATE: 2/4/22
CHECKED BY: BWA DATE: 2/4/22
APPROVED BY: BWA DATE: 2/4/22

SEAL:

URS
12420 MILESTONE CENTER DR., SUITE 150
GAITHERSBURG, MD 20878
(301) 820-3000

TAYLOR RUN STREAM STABILIZATION
BIOENGINEERING DESIGN
EXISTING CONDITIONS

DRAWING
EX – 01
SCALE 1"=40'
SHEET 1 OF 5

C:\Users\sara.tolnay\Desktop\Alexandria\CAD\Taylor Run Design Files\20-SHEETS\EXISTING CONDITIONS AND DEMO PLAN OVERALL_BIO.dwg Plotted: 3/11/2022 2:47 PM by Tolnay, Sara