APPENDIX G

POLLUTANT REMOVAL SUMMARY

wood.

APPENDIX G. POLLUTANT REMOVAL SUMMARY TABLE

		BANCS ASSESSMENT											Interim Rates			
Project Site	**Physiographic Province**	Assessment Length (ft)	TSS (ton/yr)	TSS (lb/yr)	Stream Restoration Efficiency (%)	$TSS_{EFFICIENCY}$ (lb/yr)	TP lb/ton sediment	TN lb/ton sediment	TP Credited (lb/yr)	TN Credited (lb/yr)	Delivery Ratio (%)	TSS Credited (lb/yr)	Approximate Project Length	TP (lb/yr)	TN (lb/yr)	TSS (lb/yr)
000109 Holmes Run	Piedmont	Pollutant Removals - Not Applicable - Unlikely to Quality for Pollutant Reductions														
000166 Holmes Run	Piedmont	50	37.74	75,480.00	50	37,740	1.05	2.28	19.81	43.02	18.1	6,830.94	100	6.80	7.50	4,488.00
Dual 90 in. Cameron Run	Coastal Plain	Pollutant Removals - Not Applicable - Unlikely to Quality for Pollutant Reductions														
Holmes Run	Piedmont	1,307	805.24	1,610,480.00	50	805,240	1.05	2.28	422.75	917.97	18.1	145,748.44	2,136	145.25	160.20	95,863.68
JBFNC Holmes Run	Piedmont	Pollutant Removals - Not Applicable - Unlikely to Quality for Pollutant Reductions														
Strawberry Run	Piedmont	816	653.85	1,307,700.00	50	653,850	1.05	2.28	343.27	745.39	18.1	118,346.85	880	59.84	66.00	13,314.40
Taylor Run	Coastal Plain	1,295	562.35	1,124,700.00	50	562,350	1.05	2.28	295.23	641.08	6.1	34,303.35	1,807	122.88	135.53	27,339.91
Timber Branch	Coastal Plain	737	666.60	1,333,200.00	50	666,600	1.05	2.28	349.97	759.92	6.1	40,662.60	1,043	70.92	78.23	15,780.59
Unnamed Walleston Trib	Coastal Plain	850	439.27	878,540.00	50	439,270	1.05	2.28	230.62	500.77	6.1	26,795.47	1,213	82.48	90.98	18,352.69
									1,661.65	***3,608.16***		***372,687.65***		***488.17***	***538.43***	***175,139.27***

NOTE: Table does not take into account baseline reductions.